

All materials and associated aggregates shall be in accordance with the Material Specifications Section as most recently revised.

All copper connections shall be flared.

All HDPE connections shall be fusion.

Service line shall be one piece with no joints.

Tracer wire shall be installed along the entire length of the HDPE service line and into the meter pit.

Connection of adapters, bends or fittings in HDPE service line shall be fusion.



Valve box shall be screw-type adjustable.

Valve box shall be installed plumb and set to finished grade

Valve box shall be iron. Plastic shall not be permitted.

Curb stop in an area subject to vehicular traffic will require the installation of a concrete collar.

Curb stop in an area subject to vehicular traffic will require the approval of the Chief Engineer.

 <p>www.metcom.org</p>	APPROVED	REVISIONS		ST. MARY'S COUNTY METROPOLITAN COMMISSION STANDARDS FOR PUBLIC WATER, SEWER AND INCIDENTAL STRUCTURES
	 DAVID J. ELBERTI, P.E. CHIEF ENGINEER	DATE	INITIALS	
	DATE: 5/11/11	6/18/09	J.E.C.	
		5/5/11	J.E.C.	STANDARD NO. W-9