



CONCRETE SHALL BE MDOT SHA MIX #2, 3000 PSI IN 28 DAYS.  
 CONCRETE SHALL BE PLACED AGAINST UNDISTURBED SOIL.  
 CONCRETE ANCHOR SHALL BE PLACED ON DOWNGRADE SIDE OF BELL.  
 ROOFING FELT SHALL BE PLACED BETWEEN THE PIPE AND CONCRETE.  
 ACTUAL DIMENSIONS OF THE ANCHOR MAY BE ADJUSTED AT THE DIRECTION OF THE ENGINEER.

|  |   |                  |          |   |
|--|---|------------------|----------|---|
|  | <b>APPROVED</b>                                 | <b>REVISIONS</b> |          | <b>ST. MARY'S COUNTY<br/>         METROPOLITAN COMMISSION</b><br>STANDARDS FOR PUBLIC WATER, SEWER<br>AND INCIDENTAL STRUCTURES |
|  | <br>C. I. FREDERICK JR., P.E.<br>CHIEF ENGINEER | DATE             | INITIALS |   |
|  | DATE: 7/1/09                                    | 6/18/09          | J.E.C.   | TYPICAL CONCRETE PIPE ANCHOR<br>PIPES 6" THRU 12"   |
|  |   |                  |          | <b>STANDARD NO. G-10</b>  |